

T E S T C E R T I F I C A T E

ST-24-08-01-01

Product: "Laminate Flooring 7,5 mm derzsiz - without bevel"

Producer: AGT Agac Sanayi ve Tic. A.S.
Organize Sanayi Bölgesi
S.Kisim, 35. Cadde
07190 DÖSEMEALTI, ANTALYA
Turkey

Order: Determination of Laminate Flooring Topical Moisture Resistance
according to ISO 4760:2022-05

Test report: 2724387

Test results:

Property	Result	Evaluation according to EN 13329:2023-12, table 3
Water resistance according to ISO 4760:2022-5	Qualitative recovery swell rating (final average): 1 Recovery swell (final average): 0,02 mm	Additional requirements according to table 3 are fulfilled
Resistance of mechanical joints to water leakage according to ISO 4760:2022-05, Annex D	No water leak through the joints after 24 h water exposure	Additional requirement according to table 3 is fulfilled

Dresden, 01/08/2024



Head of laboratory




Engineer in charge

T E S T C E R T I F I C A T E

ST-23-07-06-01

Product: Laminat Flooring "8 mm - derzli / with bevel"

Producer: AGT Agac Sanayi ve Tic. A.S.
Organize Sanayi Bölgesi
S.Kisim, 35. Cadde
07190 DÖSEMEALTI, ANTALYA
TÜRKIYE

Order: Determination of Laminate Flooring Topical Moisture Resistance
according to ISO 4760:2022-05

Test report: 2723297


Test results:

Property	Result	Evaluation according to prEN 13329:2023, table 3
Water resistance according to ISO 4760:2022-5	Qualitative recovery swell rating (final average): 2 Recovery swell (final average): 0,19 mm	Additional requirements according to table 3 are fulfilled
Resistance of mechanical joints to water leakage according to ISO 4760:2022-05 annex D	No water leak through the joints after 24 h water exposure	Additional requirements according to table 3 are fulfilled

Dresden, 06/07/2023



Head of laboratory



Engineer in charge

T E S T C E R T I F I C A T E

ST-23-07-06-02

Product: Laminate Flooring "8 mm - derzsiz / without bevel"

Producer: AGT Agac Sanayi ve Tic. A.S.
Organize Sanayi Bölgesi
S.Kisim, 35. Cadde
07190 DÖSEMEALTI, ANTALYA
TÜRKIYE

Order: Determination of Laminate Flooring Topical Moisture Resistance
according to ISO 4760:2022-05

Test report: 2723297

Test results:

Property	Result	Evaluation according to prEN 13329:2023, table 3
Water resistance according to ISO 4760:2022-5	Qualitative recovery swell rating (final average): 1 Recovery swell (final average): 0,00 mm	Additional requirements according to table 3 are fulfilled
Resistance of mechanical joints to water leakage according to ISO 4760:2022-05 annex D	No water leak through the joints after 24 h water exposure	Additional requirements according to table 3 are fulfilled

Dresden, 06/07/2023

Adrian Moser

Head of laboratory



J. J. J.

Engineer in charge

T E S T C E R T I F I C A T E

ST-23-08-16-01

Product: Laminat Flooring "8 mm - Şilteli / with underlayment"

Producer: AGT Agac Sanayi ve Tic. A.S.
Organize Sanayi Bölgesi
S.Kisim, 35. Cadde
07190 DÖSEMEALTI, ANTALYA
TÜRKIYE

Order: Determination of Laminat Flooring Topical Moisture Resistance
according to ISO 4760:2022-05

Test report: 2723459

Test results:

Property	Result	Evaluation according to prEN 13329:2023, Table 3
Water resistance according to ISO 4760:2022-5	Qualitative recovery swell rating (final average): 2 Recovery swell (final average): 0,26 mm	Additional requirements according to table 3 are fulfilled
Resistance of mechanical joints to water leakage according to ISO 4760:2022-05, Annex D	No water leak through the joints after 24 h water exposure	Additional requirement according to table 3 is fulfilled

Dresden, 16/08/2023



Head of laboratory




Engineer in charge

T E S T C E R T I F I C A T E

ST-23-09-04-01

Product: Laminat Flooring "10 mm - derzli / with bevel"

Producer: AGT Agac Sanayi ve Tic. A.S.
Organize Sanayi Bölgesi
S.Kisim, 35. Cadde
07190 DÖSEMEALTI, ANTALYA
TÜRKIYE

Order: Determination of Laminat Flooring Topical Moisture Resistance
according to ISO 4760:2022-05

Test report: 2723501

Test results:

Property	Result	Evaluation according to prEN 13329:2023, Table 3
Water resistance according to ISO 4760:2022-5	Qualitative recovery swell rating (final average): 2 Recovery swell (final average): 0,25 mm	Additional requirements according to table 3 are fulfilled
Resistance of mechanical joints to water leakage according to ISO 4760:2022-05, Annex D	No water leak through the joints after 24 h water exposure	Additional requirement according to table 3 is fulfilled

Dresden, 04/09/2023



Head of laboratory




Engineer in charge

TEST CERTIFICATE

ST-23-07-06-04

Product: Laminat Flooring "10 mm - mood / with bevel"

Producer: AGT Agac Sanayi ve Tic. A.S.
Organize Sanayi Bölgesi
S.Kisim, 35. Cadde
07190 DÖSEMEALTI, ANTALYA
TÜRKIYE

Order: Determination of Laminate Flooring Topical Moisture Resistance
according to ISO 4760:2022-05 after 72 h water exposure

Test report: 2723297

Test results:


Property	Result	Evaluation according to prEN 13329:2023, table 3
Water resistance according to ISO 4760:2022-5	Qualitative recovery swell rating (final average): 1 Recovery swell (final average): 0,08 mm	Additional requirements according to table 3 are fulfilled
Resistance of mechanical joints to water leakage according to ISO 4760:2022-05 annex D	No water leak through the joints after 72 h water exposure	Additional requirements according to table 3 are fulfilled

Dresden, 06/07/2023



Head of laboratory




Engineer in charge

T E S T C E R T I F I C A T E

ST-23-07-06-03

Product: Laminat Flooring "10 mm - mood / with bevel"

Producer: AGT Agac Sanayi ve Tic. A.S.
 Organize Sanayi Bölgesi
 S.Kisim, 35. Cadde
 07190 DÖSEMEALTI, ANTALYA
 TÜRKIYE

Order: Determination of Laminate Flooring Topical Moisture Resistance
 according to ISO 4760:2022-05

Test report: 2723297

Test results:

Property	Result	Evaluation according to prEN 13329:2023, table 3
Water resistance according to ISO 4760:2022-5	Qualitative recovery swell rating (final average): 1 Recovery swell (final average): 0,13 mm	Additional requirements according to table 3 are fulfilled
Resistance of mechanical joints to water leakage according to ISO 4760:2022-05 annex D	No water leak through the joints after 24 h water exposure	Additional requirements according to table 3 are fulfilled

Dresden, 06/07/2023

Andreas Loske

Head of laboratory



[Signature]

Engineer in charge

T E S T C E R T I F I C A T E

ST-24-09-26-04

Product: Product Name: "Laminate Flooring 10 mm Şilteli - with Underlayment"
laminate floor covering acc. to EN 13329:2023-12 with integrated underlay

Producer: AGT Agac Sanayi ve Tic. A.S.
Organize Sanayi Bölgesi
S.Kisim, 35. Cadde
07190 DÖSEMEALTI, ANTALYA
Turkey

Order: Determination of Laminate Flooring Topical Moisture Resistance
according to ISO 4760:2022-05

Test report: 2724530


Test results:

Property	Result	Evaluation according to EN 13329:2023-12, table 3
Water resistance according to ISO 4760:2022-5	Qualitative recovery swell rating (final average): 2 Recovery swell (final average): 0,17 mm	Additional requirements according to table 3 are fulfilled
Resistance of mechanical joints to water leakage according to ISO 4760:2022-05, Annex D	No water leak through the joints after 24 h water exposure	Additional requirement according to table 3 is fulfilled

Dresden, 26/09/2024



Head of laboratory



Engineer in charge

T E S T C E R T I F I C A T E

ST-23-07-06-05

Product: Laminate Flooring "12 mm - derzli / with bevel"

Producer: AGT Agac Sanayi ve Tic. A.S.
Organize Sanayi Bölgesi
S.Kisim, 35. Cadde
07190 DÖSEMEALTI, ANTALYA
TÜRKIYE

Order: Determination of Laminate Flooring Topical Moisture Resistance
according to ISO 4760:2022-05

Test report: 2723297

Test results:

Property	Result	Evaluation according to prEN 13329:2023, table 3
Water resistance according to ISO 4760:2022-5	Qualitative recovery swell rating (final average): 1 Recovery swell (final average): 0,13 mm	Additional requirements according to table 3 are fulfilled
Resistance of mechanical joints to water leakage according to ISO 4760:2022-05 annex D	No water leak through the joints after 24 h water exposure	Additional requirements according to table 3 are fulfilled

Dresden, 06/07/2023



Head of laboratory



Engineer in charge

TEST CERTIFICATE

ST-23-12-11-03

Product: "Laminate Flooring 12 mm şilteli - with underlayment"

Producer: AGT Agac Sanayi ve Tic. A.S.
Organize Sanayi Bölgesi
S.Kisim, 35. Cadde
07190 DÖSEMEALTI, ANTALYA
Turkey

Order: Determination of Laminate Flooring Topical Moisture Resistance
according to ISO 4760:2022-05

Test report: 2723633

Test results:

Property	Result	Evaluation according to prEN 13329:2023, Table 3
Water resistance according to ISO 4760:2022-5	Qualitative recovery swell rating (final average): 2 Recovery swell (final average): 0,21 mm	Additional requirements according to table 3 are fulfilled
Resistance of mechanical joints to water leakage according to ISO 4760:2022-05, Annex D	No water leak through the joints after 24 h water exposure	Additional requirement according to table 3 is fulfilled

Dresden, 11/12/2023



Head of laboratory



Engineer in charge